

# Pre-Application Site Visit Report

## Project 6592656, 9202 11TH AVE NW

---

**Assessment Completed:** 4/25/2017

**Project Description:** DEMOLISH EXISTING CHURCH & SFR PER PLAN

**Primary Applicant:** [Julian Weber](#)

This report lists a preliminary assessment of project requirements based on your pre-application site visit (PASV). The PASV is completed by site inspectors from the Seattle Department of Construction and Inspections (SDCI).

### Next Steps

1. Review the requirements in this report and contact the staff members listed below with questions.
2. Schedule an appointment for permit application intake with SDCI. **Please bring a copy of this report to your intake appointment.**

### Questions About This Report

If you have questions about the information in this report, contact:  
Roxanne Kennedy, (206) 615-1283, [Roxanne.Kennedy@seattle.gov](mailto:Roxanne.Kennedy@seattle.gov)

### Other Resources

- General questions about the permit process: Contact the SDCI Applicant Services Center (ASC) at 206-684-8850.
- User-friendly guides to city permitting processes: [SDCI](#) and [SDOT](#).
- [Detailed zoning information](#).
- Visit our [permit type pages](#) for step-by-step instructions and forms for preparing your application and plans for review.

### Pre-Application Site Visit (PASV) Requirements

PASV report requirements may be subject to additions, changes, or modifications by the department. The purpose of the report is to alert the applicant that there may be unusual or complex site conditions that trigger requirements from the department regarding this project. **The applicant is responsible for providing all required documents at the intake appointment.** If you have questions about this report or the PASV process, please contact the SDCI Site Development Team at (206) 684-8860.

**Note:** Any project application associated with the development site can utilize the results from this PASV if the application is accepted by SDCI within 24 months of the above inspection date. After 24 months, the applicant must apply for another PASV. No extensions will be granted.

The site plan did not include the following existing or proposed elements:

Existing SFR on site is occupied.

### ECA Mapping Unit and Type

Non-ECA

### Earth Disturbance

If excavation has the potential to encroach on adjacent property in order to facilitate construction activity, please provide documentation of consent from the adjacent property owner. Show area of proposed encroachment on the submitted drawings and detailed cross-sections.

## **Existing ROW Conditions**

### **11TH AVE NW**

Street conditions:

Chip seal

Visible pavement width is: 24LF

Curb conditions:

No curb adjacent to site

A storm inlet does not appear to be located <350 ft from the site and prior to crossing a public right of way.

### **NW 92ND ST**

Street conditions:

Chip seal

Curb conditions:

No curb adjacent to site

A storm inlet does not appear to be located <350 ft from the site and prior to crossing a public right of way.

## **Potential Impacts to Seattle Parks Property**

No parks property in vicinity

## **Tree Protection**

Trees greater than 6 inches in diameter as measured 4.5 ft above ground are present on the site but not shown on the site plan. Show the dripline of

- 1) **all** trees on the site,
- 2) adjacent trees that encroach on the site that are greater than 6 inches in diameter as measured 4.5 ft above ground, and
- 3) **all** trees located in the adjacent ROW.

Include common and scientific names for all trees shown. For more information, see [Director's Rule 16-2008](#) and [Tip 242](#).

## **Construction Stormwater Control**

All projects with earth disturbance, regardless of size, require temporary and permanent stormwater control in accordance with the Construction Stormwater Control (CSC) Technical Requirements Manual ([DR 21-2015, Volume 2](#)).

**Show the following on the [Construction Stormwater Control and Soil Amendment Standard Plan](#):**

Place filter fabric, straw bales, straw wattles, or other approved equal to control construction stormwater runoff. Required along the following property lines:

Place compost socks, compost berms, filter fabric fencing, straw bales, straw wattles, or other approved perimeter control BMPs to eliminate construction stormwater runoff.

Show the location of a stabilized construction access to the site; show methods to eliminate uncontrolled conveyance of mud and dirt into the right of way (ROW).

Cover bare soil with compost blankets, straw, mulch, matting, or other approved equal to control construction stormwater runoff.

Cover stockpiles and bare slopes with compost blankets, tarps, matting or other approved equal to control construction stormwater runoff.

A First Ground Disturbance inspection is required before any ground disturbance related to this permit, including demolition, tree cutting, clearing, grubbing, and grading. After your permit is issued, schedule an inspection by calling (206) 684-8900 or [online](#) at <http://web1.seattle.gov/DPD/InspectionRequest/default.aspx>.

## **Inspectors Notes**

Existing SFR on site is occupied.