

# Pre-Application Site Visit Report

## Project 6611276, 401 NE NORTHGATE WAY

---

**Assessment Completed:** 8/10/2017

**Project Description:** Voluntary ADA upgrades to (E) banking center. Adjust pressure at main door, remove old millwork, enlarge viewing room to provide accessibility and replace ATM keypads, rework existing walkway and accessible parking

**Primary Applicant:** [Lewis Chu](#)

This report lists a preliminary assessment of project requirements based on your pre-application site visit (PASV). The PASV is completed by site inspectors from the Seattle Department of Construction and Inspections (SDCI).

### Next Steps

1. Review the requirements in this report and contact the staff members listed below with questions.
2. Schedule an appointment for permit application intake with SDCI. **Please bring a copy of this report to your intake appointment.**

### Questions About This Report

If you have questions about the information in this report, contact:  
Kathleen H Wilson, (206) 233-7932, [Kathleen.Wilson@seattle.gov](mailto:Kathleen.Wilson@seattle.gov)

### Other Resources

- General questions about the permit process: Contact the SDCI Applicant Services Center (ASC) at 206-684-8850.
- User-friendly guides to city permitting processes: [SDCI](#) and [SDOT](#).
- [Detailed zoning information](#).
- Visit our [permit type pages](#) for step-by-step instructions and forms for preparing your application and plans for review.

### Pre-Application Site Visit (PASV) Requirements

PASV report requirements may be subject to additions, changes, or modifications by the department. The purpose of the report is to alert the applicant that there may be unusual or complex site conditions that trigger requirements from the department regarding this project. **The applicant is responsible for providing all required documents at the intake appointment.** If you have questions about this report or the PASV process, please contact the SDCI Site Development Team at (206) 684-8860.

**Note:** Any project application associated with the development site can utilize the results from this PASV if the application is accepted by SDCI within 24 months of the above inspection date. After 24 months, the applicant must apply for another PASV. No extensions will be granted.

### ECA Mapping Unit and Type

Non-ECA

### Earth Disturbance

If temporary cuts greater than 1h:1v will be required in order to facilitate construction activity, please provide a geotechnical engineer's verification that soil conditions allow cuts to stand unsupported. Include detailed cross sections.

## **Potential Impacts to Seattle Parks Property**

No parks property in vicinity

## **Construction Stormwater Control**

All projects with earth disturbance, regardless of size, require temporary and permanent stormwater control in accordance with the Construction Stormwater Control (CSC) Technical Requirements Manual ([DR 21-2015, Volume 2](#)).

**Show the following on the [Construction Stormwater Control and Soil Amendment Standard Plan](#):**

Place silt-trapping inserts in receiving catch basins located within 10 feet of construction entrance.

Cover bare soil with compost blankets, straw, mulch, matting, or other approved equal to control construction stormwater runoff.

Cover stockpiles and bare slopes with compost blankets, tarps, matting or other approved equal to control construction stormwater runoff.

A First Ground Disturbance inspection is required before any ground disturbance related to this permit, including demolition, tree cutting, clearing, grubbing, and grading. After your permit is issued, schedule an inspection by calling (206) 684-8900 or [online](#) at

<http://web1.seattle.gov/DPD/InspectionRequest/default.aspx>.

## **Inspectors Notes**

Structure is in the NE corner of Northgate Mall, access is through the parking lot. Plot plan appears to be accurate, no unusual site conditions.